

2016-2017 Planned Projects

Repair Whiteside, Wolf Branch, and Loop Creek tennis court cracks: (03-00-517) moved to 2017-2018

2-Benches at Wolf Branch Tennis Court, (03-00-521) Completed with 1 bench

Repair trails at Centennial Park. (03-00-517) placed ag lime on west side trails, east side moved to 2017-2018

Expand parking lot at Centennial Park (03-00-811) completed 11-2016

Remove bridge and replace with culvert "safety and longevity" (03-00-517) Centennial Park. **Moved to 2017-2018**

Replace playground equipment in Loop Creek Park, (03-00-811) ordered new playground equipment 11/2016 with west side playground to be removed 12/2016 and replaced. All equipment removed/new equipment in garage to be installed spring 2017 completed

Seal Loop Creek Tennis Court Parking Lot and road (03-00-517) **completed**

Loop Creek Park Improvements. ??? (03-00-811) See Above

Replace Northland sewer lines due to subsidence: possible grant \$90,000 plus engineering cost. (08-00-851) **moved to 2017-2018**

Redo Parking lot at Sewer Plant. (08-00-511) completed 11/2016

Maintenance on sewer plant roof, includes new soffit, fascia, downspouts, and gutters. (08-00-511) completed 2016

Raise UV Panels and Ballasts (08-00-511) \$20,000 prevents further damage to control panels and ballast from flooding of Loop Creek. **Moved to 2017-2018**

Replace windows at sewer plant. (08-00-511) **moved to 2017-2018**

Maintenance on sewer plant: 08-00-511)

Phase 2 Plant #3 \$333,000 **moved to 2017-2018**

- a. Replacement of existing blowers with turbo blowers
- b. Electrical Grant app fees

Upgrade Countryview Lift Station Electrical Panel. (08-00-512) **moved to 2017-2018**

Sewer manhole and sewer line rehab, \$250,000 (08-00-851

Lining of manholes approximately

- a. 75182-75150-75156-76652 **moved to 2017-2018**

Sewer lining of problem lines; approx..\$600 per ft. includes engineering costs.

(08-00-851) **completed Nov. 2016 at**

- a. Sewer lining from manhole 76210 to 76209 (approx.. 150 ft)
- b. Sewer lining from manhole 75157 to 75186 (approx.. 200 ft)
- c. Sewer lining from manhole 75168 to 75155 (approx..300 ft)
- d. Sewer lining from manhole 75152 to 75148 (approx.. 300ft)
- e. Repair sewer line drops in Yorktown Manhole 76210-76209 (approx.. 150 ft)
- f. Todd lane sewer lining

4 inch trash / water pump (08-00-830) \$4500

Purchase a mini excavator. (08-00-830) (with our municipal discount it's cheaper to buy new than used) **moved to 2017-2018**

Purchase a smoke blower to detect infiltration into our sewer lines. (08-00-830) **moved to 2017-2018**

Smoke and televise various lines for needed repairs.

Purchase anti-bacterial cleaning system to be used on hoses on vacor truck in conjunction with cleaning sewers. Safety for Sewer workers. (08-00-830) **move to 2017-2018**

MISC. LINES NEEDING TO BE LINED: moved to 2017-2018

- a. Blanc-Lee from manhole 72038 to 72033 (08-00-851) Approx. 400 ft.
- b. Williamsburg from manhole 76211 to 76212 (08-00-851) Approx. 400 ft.
- c. NW of Lake ave. from manhole 74440 to 74459 to 74460. (08-00-851) Approx. 500 ft.
- d. Line Rockwood Ct. sewer line and manhole (08-00-851)
- e. Adeline has 2 manholes needing lined due to heavy roots. (08-00-851)
- f. S. Indiana line manhole behind house. Heavy Roots. (08-00-851)
- g. Ill. 159 by Weatherstone by house needs lining of manhole and sewer line, moderate roots. (08-00-851)

MANHOLES TO BE RAISED BY TOWNSHIP PERSONNEL:

- a. Remove metal riser ring on manhole 75156
- b. Hollyhock Ln.
- c. Raise manhole S. of Flora Ct. 71579-71578
- d. Raise manholes on Janet, Kenn, and Dennis